


NOTES:

1. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
2. PERFORM PERCOLATION TEST ON PLANTING PIT PER SPECIFICATIONS.
3. DO NOT APPLY WATER TO THE STRUCTURAL SOIL UNLESS THE TOP DRESSING IS IN PLACE.
4. EMITTERS DISTRIBUTING WATER UNDER HARDSCAPE AND IN OPEN TREE GRATE AREAS ARE ON SEPARATE VALVES.
5. CONTRACTOR TO MAKE CERTAIN THAT ALL IRRIGATION TUBING IS ALLOWING WATER TO FLOW THROUGH IT, VERIFY THAT TUBING IS NOT KINKED OR CRUSHED BY THE STRUCTURAL SOIL.
6. CONTRACTOR MAY USE NATIVE SOIL + COMPOST MIX BETWEEN VALVE BOX AND ROOT BALL TO RUN DISTRIBUTION TUBING IN AROUND TREE.



STRUCTURAL SOIL IRRIGATION DETAIL

VIEW #1 , USING MULTI-PORT EMITTER
NOT TO SCALE